

Caterpillar Tunnel Materials

for 14' x 50' house, 5' between poles

with thanks to Teresa Willman for sharing her knowledge and supplier info



| Item | Amount | Size | Cost | Supplier |
|---|---|--|--------|----------------------------------|
| Galvanized Conduit anchor rods | 10 x 10' sections, cut into 3' sections | 3/4" | 100* | Home Depot |
| Metal pipe (hoops and ridgepole) | <ul style="list-style-type: none"> • 15 x 24' galvanized fencing poles • 50' total (length of sections doesn't matter) swedged galvanized fencing poles | <ul style="list-style-type: none"> • approx. 1 3/8" • approx. 1 3/8" | 628.99 | Nordic (Saanichton) |
| Over-the-pipe-wire straps | 22 | 1-3/8" x 1-3/8" | 29.64 | Steele Greenhouse (Mayne) |
| Plastic | 1 roll | 28' x 100' (6 mil) | 313.85 | Nu-Grow (Garabaldy St, Victoria) |
| Rope | 8 packages | 7/32 x 100' | 99.92 | Slegg Lumber |
| S Hooks | 30 | 2" | 17.70 | Slegg Lumber |
| T Posts | 4 | 5' or 6' | 32* | Integrity Sales |

*= approximate cost

Also would need drill plus drill bits, hacksaw, pipe bender and lots for pairs of hands to help!

Total for materials: \$1222.10